OFFICE OF THE SUPERINTENDENT, POWER AND LIGHTING, BANGALORE.

Subject :—Tender for providing heating circuit in the kitchen of the University Union Restaurant, Palace Road, Bangalore.

Abstract Notification.

Attention is drawn to this office notification dated 29th October 1938, inviting tenders for the above work, published in Part VI, pages 1954-1955 of the *Mysore Gazette*, dated 3rd November 1938. The last date for receiving tenders is 18th November 1938, and the earnest money required is Rs. 25.

C. R. GOWDA,
Superintendent.

MYSORE STATE RAILWAY.

OFFICE OF THE DISTRICT ENGINEER, MYSORE STATE RAILWAY, BANGALORE CITY.

Notification dated 4th November 1938.

Notice is hereby given that sealed tenders will be received at the Office of the District Engineer, Mysore State Railway, Bangalore City, on any day upto 12 noon on 26th November 1938, for collecting and spreading broken stone ballast on Bangalore-Harihar Section.

An approximate estimate of quantities is given in the following schedule. The quantities are not guaranteed. The whole work should be completed by the 15th May 1939, showing continuous equal monthly progress under collection work.

2. Details of work and conditions of schedule agreement may be seen at the District Engineer's Office, Mysore State Railway, Bangalore City, on all working days between 10-30 A.M. and 4-30 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the District Engineer on payment of rupee one which will not be refunded.

4. Every tender must be accompanied by a deposit of Rs. 200 in cash as earnest money and should be superscribed "Tenders for collecting and spreading broken stone ballast on Bangalore-Harihar Section," in default of which tenders will be rejected.

5. The earnest money of the rejected tenders will be returned as early as possible after the tenders are disposed of and in the case of accepted tender, it would be held as a part of security under Clause 4 of the Schedule Agreement referred to.

6. The final acceptance of any tender will rest with the Superintendent, Way and Works, Mysore State Railway, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender or any portion of a tender.

7. The name of the contractor whose tender has been accepted will be posted on the Notice Board in the District Engineer's Office. No enquiries regarding the acceptance or rejection of a tender will be answered.

8. Within eight days of the acceptance of the tender, the successful competitor is required to execute the usual schedule agreement, in default of which his tender will be considered as cancelled and the earnest money will be forfeited to Government.

9. Definate rates against each item of work in the schedule should be noted both in figures and in words. Tenders may be sent up for all or for a few of the sections noted in the schedule.

10. In case the accepted tenderer quarries, ballasts, etc., from Railway, Government or Forest land for use in this work, Royalty at the rates fixed by the Government will be recovered from his bills.

11. The whole of the work specified in the agreement to be completed as specified in para 1 above, failing which or failing to carry out any of the conditions of the agreement, the whole of the money held in deposit or so much of it as the General Manager considers proper will, without prejudice to any other legal or equitable right or remedy which the General Manager may have, be absolutely forfeited to the General Manager.

12. Should any dispute arise in the interpretation of the clauses of the tender or in respect of any items of work or specification, the decision of the Superintendent, Way and Works, shall be final.

13. The work of collection of metal ballast should be completed by the end of March 1939.

14. Contractors should specify for each section separately, the depots of collection and the quantity they propose to collect at each depot.

Schedule.

Items of work	Unit	Quantity	Rate	Cost
1. Collection of broken stone ballast, quartz or granite, broken to pass through a 2" diameter ring in all directions and must not pass through a ring of ¾" dia. including stacking the same in standard heaps of 50'×20'×2' or 50'×10'×2' absolutely free from earth and dust, wherever shown on prepared level ground inclusive of all charges within Railway limits .. Pebbles must on no account be mixed by quarrying or by field picking.	C.ft. 1,000	C.ft. 3,65,000		

Items of work	Unit	Quantity	Rate	Cost
The ballast must be collected at nil points on line and on no account over cuttings more than three feet deep, or near banks over three feet high. Platforms should be got passed before starting collection. The collection at each place should not be less than a train load, *i.e.*, 3,000 C.ft. and heaps should be built parallel to the line for the full length of the train to facilitate loading.	C.ft.		Rs. a. p.	
Section — *Depots* — *Quantity*: Tumkur .. Mile 198 .. 20,000 C.ft.; ,, 188 .. 18,000 ,,; ,, 177 .. 18,000 ,,; ,, 172 .. 18,000 ,,; Nittur .. ,, 143–20 .. 15,000 ,,; ,, 142–16–19 .. 15,000 ,,; ,, 132–10–12 .. 14,000 ,,; Arsikere .. ,, 111–19–22 .. 18,000 ,,; ,, 105–8–9 .. 18,000 ,,; ,, 100–8–9 .. 18,000 ,,; Shivani .. ,, 80–8–10 .. 26,000 ,,; ,, 60–0–4 .. 26,000 ,,; ,, 55–13–17 .. 26,000 ,,; ,, 47–4–7 .. 26,000 ,,; Davangere .. ,, 28–7–9 .. 44,000 ,,; ,, 14–1–7 .. 45,000 ,,				
2. Loading into and unloading from ballast train for loads under 20 miles	1,000 C.ft.	3,65,000		

M. RAMAIYA,
District Engineer.

OFFICE OF THE DISTRICT MEDICAL OFFICER, MYSORE STATE RAILWAY, MYSORE.

Notification dated 4th November 1938.

Sealed tenders for the removal (on contract) of night-soil and rubbish at the following stations from 1st January 1939, for a period of one year, will be received at the following stations on the dates and time specified against them.

BANGALORE CITY.

(1) Night-soil ..	.. Separate sealed tender should be presented to the Assistant Surgeon, Railway Dispensary, Bangalore City, at 9 A.M. on 9th December 1938.
(2) Rubbish, etc., in the Metre and Broad Gauge areas.	Separate sealed tender should be presented to the Assistant Surgeon, Railway Dispensary, Bangalore City, at 9 A.M. on 9th December 1938.

ARSIKERE.

Rubbish and Night-soil	.. Sealed tender should be presented to the Assistant Surgeon, Railway Dispensary, Arsikere, at 10 A.M. on 12th December 1938.

The contractor shall remove the rubbish collected in the dust-bins twice a day before 8-30 A.M. and 4-30 P.M. in carts, owned or hired. This rubbish should not be thrown anywhere in the station premises or within the municipal limits, nor on the road side.

The night-soil collected in covered drums to be removed, in closed carts, far away from any dwelling areas, and deposited in trenches. The contractor is responsible for the cleanliness of the areas.

Each tender must be accompanied by a deposit of Rupees Twenty-five which in the case of unsuccessful tenderers will be returned.

The successful tenderer should sign an agreement on stamped paper which can be obtained on payment of a small fee of Re. 0–10–0 from the Auditor, Mysore State Railway, Mysore.

Further particulars, if any, may be obtained from the Assistant Surgeons, Railway Dispensaries Bangalore City and Arsikere.